

NOTES:

- 1. METER MANIFOLD MAY BE EXTENDED UP TO A MAXIMUM OF SIX (6) METERS.
- 2. METER YOKE AND BOX DETAIL AT W-2A (3/4" AND 1" RESIDENTIAL TAP AND WATER SERVICE DETAIL).
- 3. ALL MATERIALS MUST CONFORM TO CITY OF ST. AUGUSTINE LIST OF APPROVED MATERIALS AND MANUFACTURERS, OR PRE-APPROVED EQUAL.
- 4. ALL FITTINGS TO BE BRASS, UNLESS SPECIFICALLY APPROVED OTHERWISE BY THE CITY.
- 5. CONTRACTOR TO PROVIDE AND INSTALL ALL MATERIALS EXCEPT THE WATER METER. CITY OF ST. AUGUSTINE WILL INSTALL THE WATER METER IN THE METER BOX ASSEMBLY THAT IS FULLY CONSTRUCTED BY THE CONTRACTOR IN ACCORDANCE WITH THIS DETAIL.



MANIFOLD INSTALLATION FOR MULTIPLE SMALL METERS (LIMIT 3 METERS)

REVISION DATE:	FEB 2017
NOT TO SCALE	W-3