

# CONSTRUCTION PROJECT INFORMATION FLYER CITY OF ST. AUGUSTINE

## Project Goal: South Dixie Highway Box Culvert Replacement

This project is in the City's Capital Improvement Plan FY18-22. The existing box culvert on South Dixie Highway that is located over Oyster Creek is aged and in need of replacement. It currently sits within the 100-year floodplain and is subject to periodic flooding. Additionally, during Hurricane Matthew, this box culvert sustained damage that resulted in weight limit restrictions to be put in place. This project will replace the existing box culvert, raise it to reduce flooding, provide drainage improvements and re-locate the existing utilities.

#### **Project Improvements**

AWA Contracting Company Inc. and crews will be performing the following work:

- Replace and elevate existing box culvert
- Raise the portion of the road associated with the box culvert
- Relocate existing utilities (water and sewer main)
- Provide improved stormwater drainage
- Milling and resurfacing of the road segment (approximately 1,300 linear feet)

**Note:** A portion of South Dixie Highway will be closed for the duration of the construction. A MAINTENANCE OF TRAFFIC PLAN will be in place to direct traffic flow during the Road Closure. This will affect both northbound and southbound traffic on South Dixie Highway. Traffic will be re-routed as follows: northbound traffic on South Dixie Highway (from SR 207) will be routed through Anderson and Spencer Streets; southbound traffic on South Dixie Highway (from W. King St.) will be routed through Lewis Blvd. Please follow road closure and detour signs and plan accordingly.

#### **Project Approved**

By the St. Johns River Water Management District on June 13, 2017. By the City Commission on September 20, 2017 for the 5-Year Capital Improvement Plan (CIP); and September 25, 2017 for the St. Johns River Water Management District Cost Share Agreement.

#### **Questions Concerning the Project**

Project Coordinator: Jessica Beach (COSA)

Phone: 904-209-4227 or

Public Works Main Number: (904) 825-1040 E-mail Address: jbeach@citystaug.com

Construction Project Manager: James Wheeler (COSA)

Phone: 904-209-4276

E-mail Address: jwheeler@citystaug.com

### **Project Contractor**

AWA Contracting Company, Inc.

Office Number: (904) 262-4157

#### **Project Schedule**

Start Date: January 3, 2018

Completion Date: May 3, 2018

<u>Project Overview</u>: This project was approved by the St. Johns River Water Management District's Governing Board for Cost Share funding for the District's General Cost Share Program for FY17-18. As such, up to 33% of the construction costs will be covered as part of this cost share program. During construction, a portion of South Dixie Highway will be closed where the box culvert is located over Oyster Creek (just south of the intersection of Pellicer LN and S. Dixie Highway). The contractor will make every effort to expedite the project to minimize the road closure and we ask for your patience during this time. A maintenance of traffic plan will be in place, including signage, messaging boards and routing of traffic. Work hours will be Monday – Friday, 7:00 AM – 5:30 PM. The enclosed project map shows the road closure location and traffic routing. Please plan accordingly and we appreciate your patience.

## **Stormwater Utility Friendly Reminder**

Help reduce environmental contamination by calling the Public Works Department at 825-1040 and reporting cave-ins, unusual amounts of standing water, clogged drains; illegal disposing of lawn debris, paint, oil, gas or any other items into the drainage system.



## CONSTRUCTION PROJECT INFORMATION FLYER CITY OF ST. AUGUSTINE



South Dixie Highway Box Culvert Replacement Road Closure and Traffic Routing Map

### **Stormwater Utility Friendly Reminder**

Help reduce environmental contamination by calling the Public Works Department at 825-1040 and reporting cave-ins, unusual amounts of standing water, clogged drains; illegal disposing of lawn debris, paint, oil, gas or any other items into the drainage system.