

CONSTRUCTION PROJECT INFORMATION FLYER CITY OF ST. AUGUSTINE

Project Goal: Smoke Testing of Sanitary Sewer in Service Areas of the City Sewer Mains

This project is part of the City's ongoing Inflow and Infiltration (I&I) Elimination Program of the Sanitary Sewer Collection System. Smoke testing of the collection systems will help identify sources of storm water runoff or ground water intrusion entering the City sewage collection system. Results from this testing will define potential sources of and elimination or minimization of unwanted storm or ground water entering sewer collection system. Elimination or minimizing of storm water flows into the collection system will help reduce or eliminate some of the causes for sewage overflows in the City and the cost of sewage treatment by reducing the volume of sewage to be treated.

Project Requirements

The City has contracted with USSI, LLC to perform Smoke Testing on several sewage collection Basins in the City.

- Coordinate and notify emergency response providers of smoke testing.
- Plan and execute traffic maintenance where testing is being performed.
- Generate and handout notices of testing to residences and businesses that are within the collection system boundaries that will be tested.
- Inspect and report the condition of Manholes.
- Measure and insert rain dishes in manholes that are within the proximity where high tides and storm flooding occurs to reduce storm or tidal flow from entering manholes.
- Identify any cross connections between the Sanitary and Storm sewers so they may be separated.
- Identify rain gutters discharging into the sanitary system so that this un-authorized inflow into the collection system may be disconnected.
- Identify any Main or Service lateral cleanouts with missing or damaged caps and plugs so they may be replaced and reduce storm water inflow into the collection system.

Note: Testing will not interrupt sanitary sewer services. Project success will require the coordination and cooperation of all businesses, residences, City personnel and emergency responders during testing and inspections.

Project Approved

Project funds for this work are included with the City's annual I&I Elimination program budget for 2023/2024.

Questions Concerning the Project

Project Coordinator and Manager: Isaac Kiltz (COSA)

Phone: (904) 201-2839 or

Public Works Main Number: (904) 825-1040

E-mail Address: ikiltz@citystaug.com

Project Contractor

USSI, LLC. Office Number: (941) 926 - 2646

Project Schedule

Manhole Inspections: June 3rd – July 19th

Door Hangers: First week of June

Smoke Testing:

Basins:

2, 3, 16, 17, & 20 June 3rd – 7th

Basins:

7, 15, 49, & 84 June 10th – 14th

Basins:

1, 8, 9, 29, 33, 65, & 66 June 17th – 21st

Basins:

4, 5, 6, 21, 22, 23, & 42 June 24th – 28th

Basins:

10, 11, 12, & 24 July 1st – 5th

Basins:

50, 51, 52, & 56 July 8th – 12th

Basins:

58, 60, & 64 July 15th – 19th

Project Overview: Smoke testing will be performed in 34 Sanitary Sewer Collection Basins which are located inside and outside of the incorporated limits of the City of St. Augustine in St. Johns County Florida. Smoke testing is an ongoing City sanitary sewer inflow and infiltration elimination program component.

Refer to map for the general locations of the basins that are scheduled for testing.